



HANSE 430e

BY TOM DOVE

» Once the term “mid-size cruiser” was used to describe boats from 30 to 35 feet, but many of today’s popular “mid-size” boats are larger. The new 43-foot Hanse 430 is performance oriented, as might be expected; it was designed by Judel/Vrolik, designer of Alinghi’s America’s Cup boats. As I found during my test sail in Miami, the 430e (epoxy) is a quick cruiser rather than a racer.

CONSTRUCTION

Hanse offers buyers of the 430 a choice between polyester resin (standard) and epoxy resin (optional). My test boat had the advantages of epoxy; the lighter weight, greater strength, and imperviousness to osmotic blistering convince some buyers to go with the optional 430e version. Both versions are built of hand-laid glass with coring above the waterline and in the deck. The epoxy version is built of post-cured prepreg cloth with a Core-cell foam core in the hull; the standard polyester version is cored with end-grain balsa.

DECK AND COCKPIT

The sailplan features what is essentially a masthead rig (though Hanse describes it as a “nine-tenths” fractional rig) with a self-tacking jib. The single jibsheet leads to a traveler track, then up the mast and down again before running aft to the cockpit. This long routing yields a better sheet lead. As

an aging lightweight, I appreciated the ample Lewmar 46 winches on the cabintop, one of which was electric—a worthwhile option on a boat with this much mainsail. The wide cockpit accommodates skippers and crews of various sizes with varying seating preferences. It’s easy to move around anywhere on the deck, thanks to low coamings, secure footing, and covered lines leading from the mast to the cockpit. The open transom makes loading and unloading people and parcels to a dock or dinghy simple.

UNDER SAIL: In the open ocean off Miami in 12 to 14 knots of wind, our test boat—which had the optional shoal-draft keel (5 feet, 11 inches versus 7 feet, 3 inches)—clicked off a steady 7-plus knots with an easy motion through light chop. The boat tacked effortlessly through 80 degrees as the self-tending jib eliminated any need to pull lines. The helm felt secure, with no hint of stalling when we heeled in the puffs. Bearing off, boatspeed climbed to better than 8 knots, and I enjoyed the same excellent directional stability and easy control. The dual wheels and good cockpit design gave me several comfy places to sit both to windward and to leeward. It was a fine sail in these typical East Coast conditions, and the 430e was fast, stable, and responsive.

UNDER POWER: Running the engine at 2,200 RPM produced 7.3 knots of boatspeed with minimal noise in the main cabin. Our test boat had a retractable bow thruster, which made maneuvering around docks absurdly simple. The boat also made whiplash turns within one boatlength and stopped and backed straight, with excellent control, even in a crosswind.

BOAT REVIEW: HANSE 430e

ACCOMMODATION

The Hanse 430 has a distinctly modern interior, especially with the optional cherry finish. The standard mahogany interior with white bulkheads does give a nod to the past, but nobody will mistake the accommodation space for a Herreshoff design. Cabinetry is flush-surfaced and precisely fitted, and the grabrails outboard of the seats blend so neatly into the decor that the skipper may need to point them out to guests. While this boat is unquestionably strong and seaworthy enough to cross oceans, the interior makes it clear that its main mission is stylish cruising. Note that voyaging will call for leechcloths on the bunks, higher countertop fiddles, and positive latches on the cabin sole. Hanse lets buyers choose among berth configurations (standard V-berth or offset Pullman berth, with or without a pilotberth) for both the forward and aft cabins; another choice is between one or two cabins aft.




The saloon sitting area can be configured in several ways, including with this small table



The galley layout, like the rest of the boat, is both stylish and functional



Dual aft cabins with large double berths are the most common guest-cabin layout



The forward cabin with ensuite head is worthy of being called the "owner's cabin"



The elegantly modern saloon styling makes it a pleasant space to hang out

VITAL STATISTICS

HEADROOM: Saloon, 6' 5"; aft cabin, 6' 2"; forward cabin, 6' 2" » **BUNKS:** Aft cabin, 5' 4" x 6' 5"; forward cabin, 6' x 6' 5" Settee, 6' 7"; cockpit seats, 1' 5" x 6' 4"

SPECIFICATIONS:

PRICE: \$369,900 (standard sailaway, FOB Baltimore, MD) includes sails, major electronics (chartplotter, speed, wind, depth), and ground tackle

BUILDER: Hanse Yachts, Greifswald, Germany; www.hanse-yachts.com

DESIGNER: Judel/Vrolik

U.S. IMPORTER: Hanse Yachts USA, Annapolis, MD; 410-626-1493

LOA: 43' 7" » **LWL:** 39' 4" » **BEAM:** 13' 9"

DRAFT: (std/opt) 5' 11"/7' 3"

DISPLACEMENT: (approx.) 22,958 lbs

BALLAST: (approx.) 7,064 lbs

SAIL AREA: (main and jib): 1,098 sq ft

POWER: 40-hp Yanmar with saildrive

TANKAGE FUEL/WATER/WASTE: 58/84/14 gal


ELECTRICAL: 220 aH (house) plus 80 aH (engine)

DISPLACEMENT-LENGTH RATIO: 169

SAIL AREA-DISPLACEMENT RATIO: 20.3 (100% foretriangle)

BALLAST-DISPLACEMENT RATIO: 31%

CERTIFICATION: CE Category A (Ocean)



OUR TAKE

PROS:

- Smooth, speedy performance
- Positive, easy control under power or sail
- Simple tacking due to the self-tending jib
- Clean, simple interior design with clever details
- Light, strong quality construction

CONS:

- Needs a step or two on mast to reach boom more easily
- Full cockpit enclosure makes access to aft end of boom difficult
- Will require small modifications for extended offshore sailing

CONCLUSION:

There are many vessels to choose from in this size range, but the Hanse 430 stands out for its modern looks, good performance, and cruising comfort. It's an excellent example of what a modern family cruiser should be.